





the measured diameter or shape is on-line real-time fed to said control system; and

said control system generates a control signal based on the measured preform diameter or shape, its deviation from the predetermined nominal preform value, and said nominal preform value,

for controlling said process in face of the deviation of the preform diameter or shape.

23. (canceled)

24. (previously presented) The process as claimed in claim 21, further including the steps of:

generating control signals based on the preform measurement, the fiber measurement, the deviation of the preform measurement from the predetermined nominal preform value, the deviation of the fiber measurement from the predetermined nominal fiber value, the predetermined nominal preform value and the predetermined nominal fiber value, for said optical fiber drawing process control;

whereby further to maintain the robust performance of said drawing process and to provide the robust quality of said optical fiber in presence of the deviations of said outer diameter or shape of said preform.

25. (previously presented) The process as claimed in claim 21,

wherein the position of measuring the optical fiber is at a position at which shrinkage of the outer diameter of said optical fiber is not larger than a predetermined allowable diameter deviation value of said optical fiber;

said control system generates control signals to control the drawing speed of said fiber from the melting preform and the feeding speed of said preform into the furnace, based on the measured preform outer diameter or shape, its deviation from the predetermined nominal preform value, said predetermined nominal preform value, the measured optical fiber outer diameter, its deviation from the predetermined nominal fiber value, and said predetermined nominal fiber value; and

the drawing process being carried out at said drawing speed and said feeding speed.

26. (previously presented) A drawing process for producing an optical fiber comprising the steps of:

heating and melting a preform in a furnace for the optical fiber;

while heating and melting, drawing said optical fiber from said preform under tension to form said optical fiber;

measuring the outer diameters of said optical fiber, which is bare before coating, at two or more different locations by respective measurement devices before the coating,

wherein a first location is close to the furnace, and

a second location is below the first location, at this second location shrinkage of the outer diameter of said optical fiber, while stretched under the drawing, is not larger than a predetermined allowable bare fiber diameter deviation value of said optical fiber, or immediately before the coating;

coating said optical fiber;

wherein said control system

calculates the deviation of the measurement of the first measurement location from the first preselected nominal value, and the deviation of the measurement of the second measurement location from the second preselected nominal value, and

whereby to maintain robustly controlled performance of said optical fiber drawing process and robust quality of said optical fiber by double monitoring the changes of the bare fiber diameters.

28. (previously presented) The process as claimed in claim 26, further including a measurement of the outer diameter of said preform above the heating and melting; providing said control system with the measured outer diameter of said preform;

wherein the control of the preform feeding speed and the fiber drawing speed of said drawing process is further based on the measured preform outer diameter, its deviation from a preselected nominal preform diameter, and said nominal preform diameter, in addition to the calculated deviations of the bare fiber.

29. (canceled)

30. (previously presented) A control method for an optical fiber drawing process control

including the steps of:

measuring a preform outer diameter by a measurement device located before a heating and melting stage, in which the preform is fed and is changing its geometrical size substantially to form said optical fiber by drawing;

measuring said optical fiber by an outer diameter measurement device located after said heating and melting stage;

providing the preform measurement and the fiber measurement into a control system which controls a feeding speed of said preform into the heating and melting stage and a drawing speed of said fiber;

calculating a preform diameter deviation of the measured preform diameter from a preselected nominal preform diameter value, and a fiber diameter deviation of the measured fiber diameter from a preselected nominal fiber diameter value;

generating control signals based on the preform deviation and the fiber deviation for said optical fiber drawing process control; and







35. (previously presented) The control method in claim 32, wherein

said control signals are further based on the measured preform diameter and the preselected nominal diameter in addition to the preform diameter deviation;

whereby to robustly control performance of said drawing process and quality of said optical fiber diameter against the deviation of the preform, various disturbances and perturbations affecting on the bare fiber diameter in the fiber drawing process.

36. (previously presented) The control method as claimed in Claim 35, wherein the control signals are further based on historical measurement data of the preform and the bare fiber being drawn over a period;

whereby the process control provides robust performance of the drawing process and robust quality of the fiber further against the fluctuations of the diameters, time-lag and time-lead of said measurements corresponding to the heating and melting stage, and environment fluctuations of the heating and melting.